

ADDENDUM NO. 1

2014
HANDICAPPED ACCESSIBLE RAMP
INSTALLATION PROJECT B

Bensalem, PA

FOR

BENSALEM TOWNSHIP

FILE NUMBER
0907.2756.00

September 26, 2014

ACKNOWLEDGE RECEIPT OF ADDENDUM NO. 1 BY SIGNING AND FAXING THE
ADDENDUM COVER SHEET TO BENSALEM TOWNSHIP (215) 633-3609.

Signature

Date

Company

Addendum No. 1
Bensalem Township
2014 Handicapped Accessible Ramp
Installation Project B
September 26, 2014

1.0 GENERAL

This addendum is hereby included in and made part of the Contract Drawings and Specifications whether or not attached thereto. All requirements of the original specifications and drawings shall remain in force except as modified by this Addendum.

2.0 REVISIONS/CLARIFICATIONS TO SPECIFICATIONS

REVISIONS/CLARIFICATIONS:

- .1 **Attachment No. 1**
Quantities and line items have been revised.
- .2 **Attachment No. 3**
Has been added to show work area limits
- .3 **Attachment No. 2**
Some items listed on attachment have been slightly revised due to scope of work.

ATTACHMENT #1

LOCATION OF WORK:

Bensalem Township (locations are within Township limits.)

DESCRIPTION OF WORK:

Installation of new and replacement handicapped accessible ramps per details and PennDOT Specifications (Form 408) Sections 630, 676, 802 and 804.

ESCALATOR CLAUSE: (If adopted by Municipality)

| SCHEDULE OF PRICES | | | | |
|--------------------|------------------------|------|--|------------|
| ITEM NO. | APPROXIMATE QUANTITIES | UNIT | DESCRIPTION | UNIT PRICE |
| 1 | 1500 | SF | Replacement of existing concrete within accessible ADA route areas. Contractor is to remove existing concrete as directed by Township within the municipal complex as shown on attachment no. 3 and replace per details on drawings SK-1, 2, 3, 4 & 5 and PennDOT specifications. | /SF |
| 2 | 10 | EA | Installation of 2' x 4' truncated dome pads. Contractor is to install truncated domes as directed by township on concrete replacement areas per drawings SK-3, 4 & 5 and PennDOT specifications. | /EA |
| | | | TOTAL BASE BID | |
| 3 | 100 | LF | Replacement of existing concrete curbing. Contractor is to remove existing concrete curbing as directed by Township within the municipal complex as shown on attachment no. 3 per drawings SK-1, 3, 4 & 5 and PennDOT specifications. | /LF |

TOTAL BASE UNIT COST AMOUNT (\$ _____)

in words

COMPANY NAME _____

ADDRESS _____

PHONE/FAX _____

SIGNATURE _____ DATE _____

NOTICE TO CONTRACTORS
DAVIS-BACON PREVAILING WAGE RATES SHALL BE USED ON THIS PROJECT

**BENSALEM TOWNSHIP
2014 B HANDICAPPED ACCESSIBLE RAMP PROJECT**

ATTACHMENT NO. 2

SPECIAL SPECIFICATIONS

1. REGISTRATION - Contractors and subcontractors must register with the Bensalem Building and Planning Department.
2. BID ITEMS - Bidders must bid all items in Attachment No. 1. The contract will be awarded based on the lowest total unit cost of items 1 and 2 that is submitted.
3. RETAINAGE - Retainage in an amount to be determined by the Township Engineer will be withheld at substantial completion of the project for any incomplete items of work. The retainage will be released when all items are completed.
4. COORDINATION OF TRAFFIC AND PARKING – contractor is required to secure work areas during construction until all restoration has been completed.
5. CONCRETE REPLACEMENT – the contractor must excavate designated locations as directed by township and replace existing concrete areas with new concrete per details and specifications on attachments and drawings attached to this bid package.
6. Restoration – A certain amount of grass and bituminous paving restoration will be required for each replacement. The contractor is to provide grass restoration consisting of 4” of topsoil, seed and mulch. Bituminous areas will be replaced with 4” of BCBC and 1” of wearing course. This restoration is to be included in the bid price for each item.

All disturbed areas are to be restored to their original condition which includes any areas damaged by the contractor or his associates.

7. It is recommended that the contractor not open more areas than they can complete in five days. No work area shall remain open for more than five days. Any work area open for more than five days unless weather related will be subject to a \$100/day fine for each day past the 5 days permitted. If a holiday weekend falls during the contract, the contractor shall pour all open areas for the holiday weekend. The engineer shall provide direction for this event. It shall be at the sole determination of the Township Engineer/Assistant if weather is the cause for any delay in construction that cause the area to be open for more than five days. Any and all open areas shall be barricaded and taped at the end of each day to the satisfaction of the Township Engineer/Assistant.
8. **PREVAILING WAGES – Davis – Bacon prevailing wages will be used in this contract and have been included in these specifications.**

ATTACHMENT
NO. 3

